

SECTION 01 74 00

CLEANING

PART 1 - GENERAL

1.1 SECTION INCLUDES

- A. Progress Cleaning
- B. Final Cleaning

1.2 PROGRESS CLEANING

- A. Contractor shall perform cleaning to ensure that any streets and other City and public properties are maintained free from accumulation of waste materials, dust, mud, and debris.
- B. Where required, Contractor shall wet down surfaces to lay dust and prevent the blowing of dust to nearby residences or public properties.
- C. Contractor shall keep all paved roads clean and free of dust, mud, and debris resulting from Contractor's operations. Daily cleanup throughout the job will be necessary as Contractor progresses with its Work, but extra attention to cleanup shall be made prior to weekends and holidays. Without limiting the foregoing, Contractor shall remove trench spoil along traveled ways daily; grade and vacuum broom surfaces initially where applicable and later water flush with high-pressure sprays, being careful to avoid downstream contamination.
- D. All dust, mud, spoils, and construction debris shall be removed daily from all roadways, ditches, shoulders, and private property (fills or spoils placed on private property at private property owner's written request excepted).
- E. Disposal of Materials:
 - 1. All waste materials, debris, and rubbish shall be legally disposed of at sites to be chosen by Contractor in accordance with applicable local, state, and federal regulations.
 - 2. Contractor is cautioned that the City of San Bruno and County of San Mateo have regulations governing the disposal of rubble, broken pavement, and similar materials.
 - 3. Become familiarized with the requirements of the agency having jurisdiction over any contemplated disposal site and shall comply with all such requirements.
- F. All excess soil from performance of Work shall be legally disposed at sites to be chosen by Contractor in accordance with applicable local, state, and federal regulations. If Contractor elects to dispose of soil on any private property, prior to any dumping, a letter allowing such dumping shall be obtained from the property owner and presented to City. Contractor is advised that the property

owner is required to obtain a grading permit from City. In addition, placement of fill in wetland areas is subject to permit procedures of the US Army Corps of Engineers. At the completion of Work, a letter from each affected property owner will be required releasing Contractor, City, and any City consultant from future liability.

- G. If Contractor does not properly clean the Site, in the opinion of City, then City shall have the option of using outside equipment to perform the cleanup and such cost will be withheld from the Contract Sum.

1.3 FINAL CLEANING

- A. Contractor shall execute final cleaning prior to final inspection, using only properly skilled workers.
- B. Remove grease, dust, dirt, stains, labels, fingerprints, and other foreign materials from exposed interior and exterior finished surfaces.
- C. Repair, patch, and touch up marred surfaces to match adjacent finishes.
- D. Clean interior and exterior surfaces exposed to view: remove temporary labels, stains and foreign substances, polish transparent and glossy surfaces, vacuum carpeted and soft surfaces.
- E. Clean equipment and fixtures to a sanitary condition, clean or replace filters of mechanical equipment operated during construction, clean ducts, blowers and coils of units operated without filters during construction.
- F. Clean Site.
- G. Mechanically sweep paved areas.
- H. Remove waste and surplus materials, rubbish, and construction facilities from Site.

PART 2 – PRODUCTS NOT USED

PART 3 – EXECUTION NOT USED

-END OF SECTION-